| ROOM/AREA | FLOOR | SKIRTING | DADO | WALLS | CILL | CORNICE | CEILING | SUNDRIES | | MOTES |
|---|---|--|-------------------|---|----------------------------|---------|--|---|---|-------|
| TEA KITCHENS | 2,5 mm vinyl asbestos tiles on cement screed. | 75 mm black vinyl on all walls excluding face brick cill walls. | | or sides of sinks and worktop areas to have 5 courses white glazed tiles splash | Afrormosia veneer one side | NIL | See ceiling drawing for suspended ceiling. | For fittings and accessories see drg. 02.70. | | |
| | | | | The remainder rendered and set and painted enamel to ceiling height. The Tea Kitchen in west wing to have face brick cill panel between columns to 669 mm above f.f. level. | | | | | | |
| CONFERENCE ROOM | screed | Power skirting on perimeter wall. On all other walls, 100 mm x 25 mm hardwood, stained. 20 mm quadrant, stained and placed after | | All off-shutter concrete columns to be painted P.V.A. to ceiling height. Face brick parapet wall to open areas. The remaining walls | | NIL | Ditto | 2 kw flush convector heaters on all cill walls between See Electrical Consultants' drawing. | columns. | |
| CUSTOMER ADVICE | Ditto | Power skirting on perimeter | | rendered and set and painted P.V.A. to ceiling height. Ditto | Ditto | NIL | Ditto | 2 kw flush convector heaters on all cill walls between See Electrical Consultants' drawing. | 1 columns. | |
| | | wall. All other walls to have 75 mm black vinyl skirting placed after carpet is laid. | | | | | | | | |
| ENQUIRIES | 2,5 mm vinyl asbestos tiles on cement screed. Computer type floor through- | | NII | Ditto See Partition details. | Ditto | | Ditto | 2 kw flush convector heaters on all cill walls between See Electrical Consultants' drawing. | 1 COLUMNS. | |
| TERMINALS PUNCHES MACHINE ROOM DISPATCH OPEN SHOP SHIFT LEADERS | out by specialists. | See also Partition details. | | All off-shutter columns to be painted P.V.A. to ceiling height. All brick walls to be rendered and set and painted eggshell enamed to ceiling height. | | | | | | |
| TELEPHONE EXCHANGE TAPE AND DISC STORE | Ditto | See Drywall Partition details and 75 mm black vinyl on brick walls. | 1 | See fully restrained Drywall Partition details. Partitions painted P.V.A. to ceiling height. Brick walls to be rendered and set and painted P.V.A. to ceiling height. | | | Ditto | | | |
| STATIONERY STORE FOULPMENT STORE | Ditto | Ditto | NIL | Ditto but painted full heigh | | | Off-shutter concrete painted P.V.A. | | | |
| THINKING ROOM | Ditto | | NII | Drywall Partitions painted P.V.A. to ceiling height. Brick walls to be rendered and set and painted P.V.A. to ceiling height. | | | See ceiling drawing for suspended ceiling. | | | |
| PLANT ROOM | Untinted granolithic, | 75 mm granolithic formed with 10 mm radius cove. | | Off-shutter concrete columns painted P.V.A. full height. Brick wells to have one coat plaster and painted P.V.A. tfull height. | | | Off-shutter concrete painted P.V.A. | d. | | |
| OFFICES, GENERAL | All offices to have close carpeting on cement screed. | Power skirting on all perimeter walls. All other walls or partitions to have 75 mm black vinyl skirting placed after carpet is laid. | | Brick walls to be rendered and set and painted P.V.A. to full height. Drywall | oiled and waxed. | | Off-shutter concrete painte P.V.A. | 2 kw flush convector heaters on all cill walls between See also Electrical Consultants' drawings. | en columns in non-airconditioned areas. | |
| | | | | Partitions painted P.V.A. to full height also. Face brick cill panel between columns to 669 mm above f.f. level. | | | | | | |
| | | | | | | | | | | |
| | | | | By Date REVISION | | | | | | |
| TNOTE: THE FINISHE APPLY TO ALL LEVE | | 2 TEARITON & S. | FFICES GENERAL TO | RIVE JAN'74 CILL WALLS IN TO | GHT TO 669 WWW. NOTE A | | sity of the Witw | atersrand Johannesburg FIN 1044 105 RIBB ABG 3 JUL | FASSLER ASSOCIATES - ARCHITECTS | |

JOHANNESBURG.

PARKTOWN Drawn; C.K.P.

Date; August 1973.

Checked;

Checked;